

**HT 436T' pullboxes** - meter boxes for service drops only

- Standard Drawing 34024 (new) 34024 (existing)
- Spaced less than 150' apart
- - 2" conduits

**HT 2'x4' pullboxes** - smallest typical PB found in sidewalks

- Standard Drawing 34056
- Spaced less than 250' apart
- 2 - 4" conduits & 0 - 2" conduits – Each Side
- 1 - 4" conduits & 3 - 2" conduits – Each Side

**HT 3'x5' handholes** - often not used; spring loaded lids fail

**HT 4'x6' handholes**

- Standard Drawing 34029
- Spaced less than 350' apart
- 4 - 4" conduits
- Knock outs for 2" conduits or 2 more 4" conduits
- 4 terminators 2 knock outs

**HT manholes** - only traffic-rated box

- Spaced less than 450' apart StarSew
- - 4" conduits
- - 2" conduits

**\*exceptions are sometimes made for up to 550' spacing (based on possible rodding distance)**